

INSTRUCTIONS

TYS3B56P13E2XB020

PERMISSIVE SCHEME WITH GROUND DISTANCE AND GROUND DIRECTIONAL OVERCURRENT FUNCTIONS

INTRODUCTION

Together, books GEK-100603 and GEK-90658 form the instructions for the TYSX020.

DESCRIPTION

The TYSXO2O is similar to the TYS3 Directional Comparison Permissive with Phase Distance and Ground Distance Functions, except that Zone 1 and Zone 2 Reach Ranges have been extended to 0.2 - 50 ohms. The standard TYS is 1 - 24 ohms.

ATTACHMENTS

For the TYSX020, these insertable pages supersede the corresponding text, tables and figures of GEK-90658.

Pages 1 through 6 (Table of Contents, showing GEK-100603 pages to the right, and applicable GEK-90658 pages to the left)
CS-1 through CS-9, CS-14, CS-15
Figures MO-1, M0-4, MO-5, MO-13
Tables AT-I and AT-II
Pages AT-5 through AT-7
Pages PT-3 through PT-7
Figure SE-1 (pages SE-4 through SE-10)
Pages SP-2, SP-5, SP-6

Note:

In the event that the pages of GEK-90658 not applicable to the TYSX020 are to be removed from the binder, it is important that pages such as CS-10, CS-16, MO-9, AT1 through AT-4, PT-1, PT-2, SE-3, SE-11, SP-1 of GEK-90658 be retained, rather than being removed along with the superseded pages.

These instructions do not purport to cover all details or variations in equipment nor provide for every possible contingency to be met in connection with installation, operation or maintenance. Should further information be desired or should particular problems arise which are not covered sufficiently for the purchaser's purposes, the matter should be referred to the General Electric Company.

To the extent required the products described herein meet applicable ANSI, IEEE and NEMA standards; but no such assurance is given with respect to local codes and ordinances because they vary greatly.

TABLE OF CONTENTS

| INTRODUCTION - GEA11797 | <u>PAGE</u> IN-1 of GEK-90658 |
|---|--|
| SCHEME DESCRIPTION GENERAL OPTIONS APPLICATION LOGIC DESCRIPTION Pilot Tripping Direct Tripping Line Pickup Out-of-Step Blocking Time-Delayed Distance Backup Tripping Potential Transformer Fuse Failure Protection (PTFF) Target Lamps Other Features | SD-1 SD-1 SD-1 SD-2 SD-2 SD-2 SD-3 SD-4 SD-4 SD-5 SD-6 SD-6 SD-6 |
| Outputs | SD-6 |
| DISTANCE FUNCTIONS MTG Zero-Sequence Current Compensation, K0 MG1 Zero-Sequence Current Compensation, K0 Positive-Sequence Angle of Maximum Reach, ØZ1 Zero-sequence Angle of Maximum Reach, ØZ0 MT and MTG Reach and Characteristic Shape, M1 and MG1 Reach, Reach Extension Factor, | CS-1 CS-1 CS-1 CS-2 |
| Timer II and III Settings Ground Zone 1 Characteristic, Mho or Reactance WORKED EXAMPLE (distance tripping functions) Distance Function Sensitivity REVERSE-REACHING BLOCKING FUNCTIONS, MB MB Reach | CS-4 CS-5 CS-8 |
| Zero-Sequence Current Compensation Factor, K MB Characteristic Timer Setting Positive-Sequence Voltage Compensation Factor, KV WORKED EXAMPLE (distance blocking functions) OVERCURRENT FUNCTIONS | CS-8 CS-7 CS-8 |
| IPB, Pilot Blocking IØØ, MT Supervision IM, Current Supervision I1, Line Pickup Supervision | CS-9 |
| OPTIONAL OVERCURRENT FUNCTIONS IPT, Pilot Tripping IDT, Direct Trip TOC, Time Overcurrent WORKED EXAMPLE (overcurrent functions) WORKED EXAMPLE (optional overcurrent functions) OUT-OF-STEP-BLOCKING | CS-9 CS-9 CS-10 CS-11 CS-11 CS-12 |
| MOB Characteristic Timer Setting Switch OSB-1 Setting Switch OSB-2 Setting WORKED EXAMPLE (out-of-step blocking) LOGIC TIMER SETTINGS CONTACT CONVERTER VOLTAGE | CS-12 CS-12 CS-12 CS-12 CS-12 CS-13 |

| SETTINGS LIST | PAGE CS 13 of GEV 006F0 |
|---|---|
| SETTINGS LIST A (Blank Form) | C3-13 Of GEK-90658 |
| SETTINGS LIST B (Worked Example) | CS-14 |
| Sellings List B (worked example) | CS-15 |
| HARDWARE DESCRIPTION | HD 1 of CEV ODGES |
| | |
| CASE ASSEMBLY | IID 4 |
| Construction | HD-1 |
| Electrical Connections and Internal Wiring | |
| IdentificationPRINTED- CIRCUIT BOARD MODULES | HD-1 |
| PRINTED- CIRCUIT BOARD MODULES | HD-1 |
| Basic Construction | HD-1 |
| Identification | HD-2 |
| XTM TEST PLUGS | HD-2 |
| Description | HD-2 |
| Terminal Designation | HD-2 |
| XTM Test-Circuit Connections | HD-2 |
| Test Plug Insertion | HD-2 |
| CARD EXTENDER | HD-3 |
| RECEIVING, HANDLING AND STORAGE | . HD-3 |
| INSTALLATION | HD-4 |
| Environment | HD-4 |
| Mounting | HD-4 |
| External Connections | HD-4 |
| External Connection Test | HD-4 |
| Surge Ground Connections | |
| | |
| NACOLUTE. | 110.4 |
| MODULES | |
| ACCEPTANCE TESTS | AT-1 of GEK-90658 |
| ACCEPTANCE TESTS | AT-1 of GEK-90658 AT-1 |
| ACCEPTANCE TESTS REQUIRED SETTINGS TEST EQUIPMENT | AT-1 of GEK-90658 AT-1 AT-1 |
| ACCEPTANCE TESTS REQUIRED SETTINGS TEST EQUIPMENT EQUIPMENT GROUNDING | AT-1 of GEK-90658 AT-1 AT-1 AT-1 |
| ACCEPTANCE TESTS REQUIRED SETTINGS TEST EQUIPMENT EQUIPMENT GROUNDING TEST CONNECTIONS (for text only) | AT-1 of GEK-90658 AT-1 AT-1 AT-1 AT-2 |
| ACCEPTANCE TESTS REQUIRED SETTINGS TEST EQUIPMENT EQUIPMENT GROUNDING TEST CONNECTIONS (for text only) INITIAL RELAY SETTINGS (for text only) | AT-1 of GEK-90658 AT-1 AT-1 AT-1 AT-2 AT-2 |
| ACCEPTANCE TESTS REQUIRED SETTINGS TEST EQUIPMENT EQUIPMENT GROUNDING TEST CONNECTIONS (for text only) INITIAL RELAY SETTINGS (for text only) GENERAL INSTRUCTIONS (for text only) | AT-1 of GEK-90658 AT-1 AT-1 AT-1 AT-2 AT-2 AT-3 |
| ACCEPTANCE TESTS REQUIRED SETTINGS TEST EQUIPMENT EQUIPMENT GROUNDING TEST CONNECTIONS (for text only) INITIAL RELAY SETTINGS (for text only) GENERAL INSTRUCTIONS (for text only) LEVEL-DETECTOR TESTS | AT-1 of GEK-90658 AT-1 AT-1 AT-1 AT-2 AT-2 AT-3 AT-4 |
| ACCEPTANCE TESTS REQUIRED SETTINGS TEST EQUIPMENT EQUIPMENT GROUNDING TEST CONNECTIONS (for text only) INITIAL RELAY SETTINGS (for text only) GENERAL INSTRUCTIONS (for text only) LEVEL-DETECTOR TESTS Fault-Detector Test | AT-1 of GEK-90658 AT-1 AT-1 AT-1 AT-2 AT-2 AT-3 AT-4 AT-4 |
| ACCEPTANCE TESTS REQUIRED SETTINGS TEST EQUIPMENT EQUIPMENT GROUNDING TEST CONNECTIONS (for text only) INITIAL RELAY SETTINGS (for text only) GENERAL INSTRUCTIONS (for text only) LEVEL-DETECTOR TESTS Fault-Detector Test IM Detector Test | AT-1 of GEK-90658 AT-1 AT-1 AT-2 AT-2 AT-3 AT-4 AT-4 AT-4 |
| ACCEPTANCE TESTS REQUIRED SETTINGS TEST EQUIPMENT EQUIPMENT GROUNDING TEST CONNECTIONS (for text only) INITIAL RELAY SETTINGS (for text only) GENERAL INSTRUCTIONS (for text only) LEVEL-DETECTOR TESTS Fault-Detector Test IM Detector Test IPB Detector Test | AT-1 of GEK-90658 AT-1 AT-1 AT-2 AT-2 AT-3 AT-4 AT-4 AT-4 AT-4 |
| ACCEPTANCE TESTS REQUIRED SETTINGS TEST EQUIPMENT EQUIPMENT GROUNDING TEST CONNECTIONS (for text only) INITIAL RELAY SETTINGS (for text only) GENERAL INSTRUCTIONS (for text only) LEVEL-DETECTOR TESTS Fault-Detector Test IM Detector Test IPB Detector Test TOC Detector Test | AT-1 of GEK-90658 AT-1 AT-1 AT-2 AT-2 AT-3 AT-4 AT-4 AT-4 AT-4 |
| ACCEPTANCE TESTS REQUIRED SETTINGS TEST EQUIPMENT EQUIPMENT GROUNDING TEST CONNECTIONS (for text only) INITIAL RELAY SETTINGS (for text only) GENERAL INSTRUCTIONS (for text only) LEVEL-DETECTOR TESTS Fault-Detector Test IM Detector Test IPB Detector Test IOC Detector Test IDT Detector Test | AT-1 of GEK-90658 AT-1 AT-1 AT-2 AT-2 AT-3 AT-4 AT-4 AT-4 AT-4 AT-4 AT-4 |
| ACCEPTANCE TESTS REQUIRED SETTINGS TEST EQUIPMENT EQUIPMENT GROUNDING TEST CONNECTIONS (for text only) INITIAL RELAY SETTINGS (for text only) GENERAL INSTRUCTIONS (for text only) LEVEL-DETECTOR TESTS Fault-Detector Test IM Detector Test IPB Detector Test IPB Detector Test IDT Detector Test IPT Detector Test IPT Detector Test | AT-1 of GEK-90658 AT-1 AT-1 AT-1 AT-2 AT-2 AT-3 AT-4 AT-4 AT-4 AT-4 AT-4 AT-4 |
| ACCEPTANCE TESTS REQUIRED SETTINGS TEST EQUIPMENT EQUIPMENT GROUNDING TEST CONNECTIONS (for text only) INITIAL RELAY SETTINGS (for text only) GENERAL INSTRUCTIONS (for text only) LEVEL-DETECTOR TESTS Fault-Detector Test IM Detector Test IPB Detector Test IDT Detector Test IPT Detector Test IPT Detector Test II Detector Test II Detector Test | AT-1 of GEK-90658 AT-1 AT-1 AT-1 AT-2 AT-2 AT-3 AT-4 AT-4 AT-4 AT-4 AT-4 AT-4 |
| ACCEPTANCE TESTS REQUIRED SETTINGS TEST EQUIPMENT EQUIPMENT GROUNDING TEST CONNECTIONS (for text only) INITIAL RELAY SETTINGS (for text only) GENERAL INSTRUCTIONS (for text only) LEVEL-DETECTOR TESTS Fault-Detector Test IM Detector Test IPB Detector Test IDT Detector Test IPT Detector Test IPT Detector Test I Detector Test | AT-1 of GEK-90658 AT-1 AT-1 AT-2 AT-2 AT-3 AT-4 AT-4 AT-4 AT-4 AT-4 AT-4 AT-4 AT-4 AT-4 |
| ACCEPTANCE TESTS REQUIRED SETTINGS TEST EQUIPMENT EQUIPMENT GROUNDING TEST CONNECTIONS (for text only) INITIAL RELAY SETTINGS (for text only) GENERAL INSTRUCTIONS (for text only) LEVEL-DETECTOR TESTS Fault-Detector Test IM Detector Test IPB Detector Test IPB Detector Test IDT Detector Test IPT Detector Test IPT Detector Test IPT Detector Test INDETECTOR TEST NEGATIVE-SEQUENCE DIRECTIONAL TESTS | AT-1 of GEK-90658 AT-1 AT-1 AT-2 AT-2 AT-3 AT-4 AT-4 AT-4 AT-4 AT-4 AT-4 AT-4 AT-4 AT-4 AT-4 AT-5 AT-5 |
| ACCEPTANCE TESTS REQUIRED SETTINGS TEST EQUIPMENT EQUIPMENT GROUNDING TEST CONNECTIONS (for text only) INITIAL RELAY SETTINGS (for text only) GENERAL INSTRUCTIONS (for text only) LEVEL-DETECTOR TESTS Fault-Detector Test IM Detector Test IPB Detector Test IDT Detector Test IDT Detector Test IPT Detector Test IPT Detector Test IPT Detector Test INDETECTOR TEST NEGATIVE-SEQUENCE DIRECTIONAL TESTS NT Test | AT-1 of GEK-90658 AT-1 AT-1 AT-2 AT-2 AT-3 AT-4 AT-4 AT-4 AT-4 AT-4 AT-4 AT-4 AT-4 AT-4 AT-5 AT-5 |
| ACCEPTANCE TESTS REQUIRED SETTINGS TEST EQUIPMENT EQUIPMENT GROUNDING TEST CONNECTIONS (for text only) INITIAL RELAY SETTINGS (for text only) GENERAL INSTRUCTIONS (for text only) LEVEL-DETECTOR TESTS Fault-Detector Test IM Detector Test IPB Detector Test IPB Detector Test IDT Detector Test IPT Detector Test IPT Detector Test IT Detector Test IT Detector Test IT DETECTOR TEST NEGATIVE-SEQUENCE DIRECTIONAL TESTS NT Test NB Test | AT-1 of GEK-90658 AT-1 AT-1 AT-2 AT-2 AT-3 AT-4 AT-4 AT-4 AT-4 AT-4 AT-4 AT-4 AT-5 AT-5 |
| ACCEPTANCE TESTS REQUIRED SETTINGS TEST EQUIPMENT EQUIPMENT GROUNDING TEST CONNECTIONS (for text only) INITIAL RELAY SETTINGS (for text only) GENERAL INSTRUCTIONS (for text only) LEVEL-DETECTOR TESTS Fault-Detector Test IM Detector Test IPB Detector Test IPB Detector Test IPT Detector Test IPT Detector Test IPT Detector Test IPT Detector Test INDETECTOR TEST NEGATIVE-SEQUENCE DIRECTIONAL TESTS NT Test NB Test REACH TESTS | AT-1 of GEK-90658 AT-1 AT-1 AT-2 AT-2 AT-2 AT-4 AT-4 AT-4 AT-4 AT-4 AT-4 AT-4 AT-5 AT-5 AT-5 |
| ACCEPTANCE TESTS REQUIRED SETTINGS TEST EQUIPMENT EQUIPMENT GROUNDING TEST CONNECTIONS (for text only) INITIAL RELAY SETTINGS (for text only) GENERAL INSTRUCTIONS (for text only) LEVEL-DETECTOR TESTS Fault-Detector Test IM Detector Test IPB Detector Test IPB Detector Test IPT Detector Test IPT Detector Test IPT Detector Test IPT Detector Test INDETECTOR TEST NEGATIVE-SEQUENCE DIRECTIONAL TESTS NT Test NB Test REACH TESTS M1 Test | AT-1 of GEK-90658 AT-1 AT-1 AT-1 AT-2 AT-2 AT-3 AT-4 AT-4 AT-4 AT-4 AT-4 AT-4 AT-5 AT-5 AT-5 AT-5 |
| ACCEPTANCE TESTS REQUIRED SETTINGS TEST EQUIPMENT EQUIPMENT GROUNDING TEST CONNECTIONS (for text only) INITIAL RELAY SETTINGS (for text only) GENERAL INSTRUCTIONS (for text only) LEVEL-DETECTOR TESTS Fault-Detector Test IM Detector Test IPB Detector Test IPB Detector Test IPT Detector Test IPT Detector Test IPT Detector Test IPT Detector Test INDETECTOR TEST NEGATIVE-SEQUENCE DIRECTIONAL TESTS NT Test NB Test REACH TESTS | AT-1 of GEK-90658 AT-1 AT-1 AT-1 AT-2 AT-2 AT-3 AT-4 AT-4 AT-4 AT-4 AT-4 AT-4 AT-5 AT-5 AT-5 AT-5 AT-5 AT-5 AT-5 |
| ACCEPTANCE TESTS REQUIRED SETTINGS TEST EQUIPMENT EQUIPMENT GROUNDING TEST CONNECTIONS (for text only) INITIAL RELAY SETTINGS (for text only) GENERAL INSTRUCTIONS (for text only) LEVEL-DETECTOR TESTS Fault-Detector Test IM Detector Test IPB Detector Test IPB Detector Test IPT Detector Test IPT Detector Test IPT Detector Test IPT Detector Test INDETECTOR TEST NEGATIVE-SEQUENCE DIRECTIONAL TESTS NT Test NB Test REACH TESTS M1 Test | AT-1 of GEK-90658 AT-1 AT-1 AT-1 AT-2 AT-2 AT-3 AT-4 AT-4 AT-4 AT-4 AT-4 AT-4 AT-5 AT-5 AT-5 AT-5 AT-5 AT-5 AT-5 AT-5 |
| ACCEPTANCE TESTS REQUIRED SETTINGS TEST EQUIPMENT EQUIPMENT GROUNDING TEST CONNECTIONS (for text only) INITIAL RELAY SETTINGS (for text only) GENERAL INSTRUCTIONS (for text only) LEVEL-DETECTOR TESTS Fault-Detector Test IM Detector Test IPB Detector Test IPT Detector Test IPT Detector Test IPT Detector Test IPT Detector Test INDETECTOR TEST NEGATIVE-SEQUENCE DIRECTIONAL TESTS NT Test NB Test REACH TESTS M1 Tests MT Tests | AT-1 of GEK-90658 AT-1 AT-1 AT-1 AT-2 AT-2 AT-3 AT-4 AT-4 AT-4 AT-4 AT-4 AT-4 AT-5 AT-5 AT-5 AT-5 AT-5 AT-5 AT-5 AT-5 |
| ACCEPTANCE TESTS REQUIRED SETTINGS TEST EQUIPMENT EQUIPMENT GROUNDING TEST CONNECTIONS (for text only) INITIAL RELAY SETTINGS (for text only) GENERAL INSTRUCTIONS (for text only) LEVEL-DETECTOR TESTS Fault-Detector Test IM Detector Test IPB Detector Test IPT Detector Test IPT Detector Test IPT Detector Test IPT Detector Test INDETECTOR TEST NEGATIVE-SEQUENCE DIRECTIONAL TESTS NT Test NB Test REACH TESTS M1 Tests MG1 Tests | AT-1 of GEK-90658 AT-1 AT-1 AT-1 AT-2 AT-2 AT-3 AT-4 AT-4 AT-4 AT-4 AT-4 AT-4 AT-5 AT-5 AT-5 AT-5 AT-5 AT-5 AT-5 |

| PERIO | ODIC TESTING | DT 1 | -f CEV | PAGE |
|-------|--|---------------|---------------|---------|
| | TESTING THE TYS WITH USER SETTINGS | PT-1 | of GEK- | 90658 |
| | TOLERANCE | PT-1 | | |
| • • | CURRENT-LEVEL DETECTORS | PT-1 | | |
| | IM | PT-1 | | |
| | IPB | | | |
| | TOC | PT-1 | | |
| | IDT | PT-2 | | |
| | | | | PT-3 |
| | REACHTESTS | | | PT-3 |
| | M1 | | | PT-3 |
| | MT | | | PT-4 |
| | MG1 | | | PT-4 |
| | MTG | | | PT-5 |
| | MB | | | PT-6 |
| | MOB | | | PT-7 |
| c=0\ | 11.01.1.0 | | | |
| 2FKA | ICING | SE-14 | of GEK | - 90658 |
| | SPARES | SE-1A | | |
| | WITHOUT THE CONTINUOUS MONITOR MODULE | SE-1A | | |
| | WITH THE CONTINUOUS MONITOR MODULE | SE-1A | | |
| | POWER SUPPLY MODULE | SE-3A | | |
| | | | | |
| SPEC | IFICATIONS | SP-1 | of GEK- | 90658 |
| | RATINGS | SP-1 | | |
| | BURDENS | | | |
| | CONTACT DATA | | | SP-2 |
| | REACH-SETTING RANGES | | | SP-2 |
| | REACH EXTENSION FACTOR | | • • • • • • | SP-2 |
| | OVERCURRENT-FUNCTION-SETTING RANGES | | of GEK- | |
| | TOC TIME DIAL | | U . U | 30030 |
| | SUPERVISION-FUNCTION-SETTING RANGES | SP-3 | | |
| | COMPENSATION-FACTOR-SETTING RANGES | SP-3 | | |
| | REPLICA-IMPEDANCE-ANGLE SETTINGS | SP-4 | | |
| | ADJUSTABLE LOGIC TIMERS | SP-4 | | |
| | | | | |
| | CURRENT SENSITIVITY (Phase Distance Units) | 37-4 CD 4 | | |
| | CURRENT SENSITIVITY (Frase Distance Units) | 5P-4 | | SP-5 |
| | DIMENCIONIC | • • • • • • | • • • • • • • | |
| | DIMENSIONS | | • • • • • • | SP-6 |
| | WEIGHT | • • • • • • | • • • • • • | SP-6 |
| CON | TINUOUS MONITOR MODULE | CNA | 4 -4 | . 0000 |
| CON | | | 1 of GEK | (-90658 |
| | ADDITIONAL FUNCTION | CM- | | |
| | ACCESS OF STORED DATA | CM- | | |
| | ACCESS OF STORED DATA | CM- | | |
| | Local Access | CM- | | |
| | Remote Access | CM- | | |
| | Clearing the Stored Data | CM- | | |
| | MODES OF OPERATION | CM- | | |
| | Local-Display Mode | CM- | | |
| | Serial-Data-Link-Access Mode | CM- | | |
| | CONTINUOUS MONITOR ADJUSTMENTS | CM- | | |
| | CONTINUOUS MONITOR SERIAL LINK USE | CM- | 7 | |
| ٠ | CHECKSUM | CM- | 7 | |
| | | | | |
| SOF | ΓWARE | . SO - | 1 of GEK | <-90658 |

| | <u>PAGE</u> |
|--------------------------------|------------------|
| RECLOSER RE-1 | |
| INITEGERICAL | DE 4 (CEV 00000 |
| | |
| DESCRIPTION | RE-1 |
| Basic Operation | RE-1 |
| Additional Features | RE-2 |
| APPLICATION | RF_A |
| Block Instantaneous Tripping | RE-5 |
| Selective Reclosing | UE-D |
| Synchronism Check | RE-5 |
| Synchronism Check | RE-6 |
| Delayed Reset | RE-6 |
| PAUSE Function - Dual Use | RE-7 |
| OPERATION | RE-7 |
| RLM131 Inputs and Outputs | RF-7 |
| Time Multiplier | RE-7 |
| Printed-Circuit-Board Assembly | RE-7 |
| | |
| | RE-8 |
| Programming | RE-8 |
| Read | . RE-10 |
| Power Up | RE-12 |
| Ratings | RE-13 |
| TESTING | RE-13 |
| Recloser Self Test | RE-13 |
| Functional Test | NE-13 |

LIST OF FIGURES

| Figure SD-1 Figure SD-2 Figure SD-3 Figure SD-4 Figure SD-5 | Out-of-Step Blocking Characteristic MOD 10™ Mnemonic Legend Logic and Internal Diagram Legend Logic Diagram Elementary Diagram | SD-8-9 -10-12 SD-13 |
|--|---|---|
| Figure CS-1 Figure CS-2 Figure CS-3 Figure CS-4 | Phase Distance Functions Characteristic Shapes Overreaching Function Load Coordination Typical Transmission System Time Curve Characteristics | . CS-4 |
| Figure HD-1 Figure HD-2 Figure HD-3 Figure HD-4 Figure HD-5 | TYS Relaying System, Front View TYS Relaying System, Rear View Outline and Mounting Dimensions XTM Connections for External-Connection Test for K and KVAR Away From Bus XTM Connections for External-Connection Test for K and KVAR Into Bus | . HD-6 . HD-7 W . HD-8 W |
| Figure MO-1 Figure MO-2 Figure MO-3 Figure MO-4 | Module Location Phase and Ground Distance Step/Persont Panel & Internal Switches, ABM11(-) Module Internal Switches, ADM112 Module | MO-2 of GEK-90658 MO-3 |
| Figure MO-7 Figure MO-8 Figure MO-9 Figure MO-10 Figure MO-11 Figure MO-12 | AFM13(-) Modules Front Panel and Internal Switch, AFM12(-) Module Front Panel & Internal Switch & Links, CTM12(-) Internal Switches, ETM111 Module Internal Links, IOM112 Module Front Panel Switches, ETM114 Module Front Panel, ISM11(-) Module Front Panel, ULM234 Module Front Panel, ULM258 Module | MO-6 of GEK-90658 MO-7 MO-8 MO-9 MO-9 MO-9 |
| Figure MO-13 Figure MO-14 Figure MO-15 Figure MO-16 | | MO-9 MO-10 of GEK-90658 MO-11 MO-12 |
| Figure AT-1 Figure AT-2 Figure AT-3 Figure AT-4 | Level-Detector Test Connections V1 Detector Test Connections Negative-Sequence Directional Test and MB Function Test Connections M1 and MT Reach Test Connections M61 and MTG Roach Test Connections | .AT-10 \ .AT-11 .AT-12 |
| Figure AT-8 Figure AT-8 | MG1 and MTG Reach Test Connections | .AT-16 |
| Figure SE-1 Figure SE-2 | Measuring Functions Block Diagram Service Logic | SE-11A of GEK-90658 |
| Figure CM-2 Figure CM-3 Figure CM-4 Figure CM-5 | Simplified Functional Diagram Depicting Continuous Monitor Operation Continuous Monitor Module Front Panel Serial Data Link Connection Continuous Monitor Phone Connection Connection for Multiple Continuous Monitors | CM-1 of GEK-90658 CM-3 CM-4 CM-8 CM-8 |
| Figure CM-6 | Front Panel & Internal Switches, TAM101 | CM-9 |

| Figure RE- | ·1 | External Connections, TYS/MOD10 - RLM131 | PAGE |
|--|--|--|---|
| Figure RE- Figure RE- | | Recloser Module RLM131 Recloser Front Panel & Setting Table Use of BI Contact to Block Instantaneous Trip | RE-18 of GEK-90658 RE-19 |
| Figure RE- Figure RE- | | RI (Reclose Initiate) and Delayed Reclose Connections for Two Separate Single-Shot | RE-20 |
| Figure RE- Figure PE- Figure RE- Figure RE- Figure RE- | 7 ·8 ·9 | Reclosures, Each With a Different Time Delay Connections, Synchronism Check Supervision Delay Reset for Ground Faults Pause Function, Dual Use Front Panel & Internal Links, RLM131 Module Functional Test Diagram | RE-21 RE-22 RE-22 RF-23 |
| | | LIST OF TABLES | |
| CS-I | IDT, D | irect Trip, Operate Signal | CS-10 of GEK-90658 |
| AT-I AT-III AT-IV AT-V AT-VI AT-VIII | Voltag Voltag Voltag Voltag Voltag | le Settings, Printed-Circuit-Card Switches and Links le Settings, Front-Panel Switches ge and Phase Angles for M1 Test ge and Phase Angles for MT Test ge and Phase Angles for MGI Test ge and Phase Angles for MTG Test ge and Phase Angles for MTG Test ge and Phase Angles for MB Test ge and Phase Angles for MOB Test | AT-3 AT-5 AT-6 AT-6 AT-6 |
| PT-I PT-II PT-IV PT-V PT-VI PT-VII PT-VIII | Test C Test C Currer Test C Test C | ances at Various Test-Current Levels ont and Voltage Phase Angles for M1 and MT Tests urrents for M1 Test urrents for MT Test ont and Voltage Phase Angles for MGI and MTG Tests urrents for MG1 Test urrents for MTG Test ont and Voltage Phase Angles for MB Reach Test | PT-3 PT-4 PT-4 PT-5 PT-6 |
| SE-I SE-II | Test-S Conti | ocket Pin Assignmentsnuous Monitor Point Number Assignments | SE-2A of GEK-90658 SE-3A |
| SP-I SP-III SP-IV SP-V SP-VI SP-VII SP-VIII | Overc TOC T Super Comp Adjus | -Setting Ranges -Extension Factor urrent-Function-Setting Ranges ime Dial vision-Function-Setting Ranges ensation-Function-Setting Ranges table Logic Timers r Various Reach Ranges | SP-2 of GEK-90658 SP-3 SP-3 SP-3 SP-3 SP-4 |
| RE-II RE-III | Reclos Interri Instan | sures upting Ratings of Auxiliary Relay Contacts itanteous Reclose | RE-4 of GEK-90658 RE-13 RE-15 |

CALCULATION OF SETTINGS

FORWARD REACHING DISTANCE FUNCTIONS (tripping functions, MT, MTG, M1 and MG1)

The following settings must be made:

- a. MTG zero-sequence current compensation, K0 (1-7, 0.1 step)
- b. MG1 zero-sequence current compensation, K0 (1-7, 0.1 step)
- c. Positive-sequence angle of maximum reach, ϕ Z1 (50°-85°, 5° step)
- d. Zero-sequence angle of maximum reach, \emptyset Z0 (50° 85°, 5° step)
- e. Overreaching (MT and MTG) reach, r $(2\Omega-50\Omega, 0.2\Omega \text{ step})$
- f. Overreaching (MT and MTG) reach multiplier, MULT (1, 0.25, 0.1) two separate settings on AFM133 module
- g. Overreaching (MT and MTG) characteristic shape (90°, 105°, 120°) two separate settings on UTM111 module
- h. Zone 1 (M1 and MG1) reach, r (2Ω - 50Ω , 0.2Ω step)
- i. Zone 1 (M1 and MG1) reach multiplier, MULT (1, 0.25, 0.1) - two separate settings on AFM133 module
- j Zone 1 reach extension factor, II (1-10×zone 1, 0.05 step)
- k. Zero suppression in the zero-sequence current supervision, MULT (1, 0.25, 0.1) - one setting on VMM115 module
- l. Zero suppression in the operate signal, 0(1) SUP and 0(T) SUP (0.1 1.5, 0.03 step) two separate settings on AFM217 module
- m. Timer II setting, TIMER II (0-3.1 sec, 0.1 sec step)
- n. Timer III setting, TIMER III (0-3.1 sec, 0.1 sec step)
- o. Ground zone 1 characteristic, SW2/4/5 and MG-1 SUP (Mho or Reactance) two settings: SW2/4/5 on ETM111 module and MG-1 SUP on UTM111 module

MTG Zero-Sequence Current Compensation, K₀

The MTG zero-sequence current compensation factor, K_0 , is a function of the positive- and zero-sequence impedances of the transmission line to be protected:

$$K_0 = \frac{Z_{0L}}{Z_{1L}} \tag{1}$$

Where:

 Z_{0L} = zero-sequence impedance of the line

 Z_{1L} = positive-sequence impedance of the line

The setting is made using switches located on the board of the AFM133 module (position S), Figure MO-4 in the MODULES section.

MG1 Zero-Sequence Current Compensation, K₀

The MG1 zero-sequence current compensation factor, K_0 , is a function of the positive- and zero-sequence impedances of the transmission line to be protected:

$$K0 = \frac{0.95 \times Z_{0L}}{Z_{1L}} \tag{2}$$

Where:

 $Z_{0L} = zero$ -sequence impedance of the line $Z_{1L} = positive$ -sequence impedance of the line

The setting is made using switches located on the board of the AFM133 module (position Y), Figure MO-4.

Positive-Sequence Angle of Maximum Reach, $\emptyset Z_1$

The positive-sequence angle-of-maximum-reach adjustment is common to all of the distance functions (MT, MTG, M1, MG1 and MB) and should be set to the angle that is just larger than the angle of the positive-sequence impedance of the transmission line on which the TYS system is applied. Use 85° for line angles greater than 85°. The setting is made using a switch located on the front panel of the ISM11(-) module, Figure MO-10.

Zero-sequence Angle of Maximum Reach, øZo

The zero-sequence angle-of-maximum-reach adjustment is common to the ground distance functions (MTG, MG1) and to the MB function and should be set to the angle that is just larger than the angle of the zero-sequence impedance of the transmission line on which the TYS system is applied. The setting is made using a switch located on the front panel of the ISM11(-) module, Figure MO-10.

MT and MTG Reach and Characteristic Shape, M1 and MG1 Reach, Reach Extension Factor, Timer II and III Settings

A given reach for either MT/MTG or M1/MG1 is made by selecting two separate settings on the front panel of the associated AFM133 module. The AFM133 module associated with MT/MTG is located in position "S" of the TYS chassis, and the AFM133 module associated with M1/MG1 is located in position "Y" of the TYS chassis. The dip switches associated with the "r" setting can be positioned to obtain a range of 2Ω to 50Ω , with a resolution of 0.2Ω . The rotary switch associated with the "MULT" setting can be positioned to 1, 0.25, or 0.1. The actual reach is:

actual reach = (r) (MULT),

which results in an actual range of 0.2Ω to 50Ω . Maximum sensitivity will be achieved if the lowest MULT is used, but faster operating time will be obtained for

higher fault currents if the highest MULT is used. Select the highest MULT value possible if current sensitivity is not a problem. Current sensitivity may be calculated using the equations given in the SPECIFICATIONS section.

When a "MULT" setting is selected, the rotary switch on the front panel must be set to this value and the link labeled "MULT" located on the board of the same module must be set to this value. In addition, there are three other settings that must be made on different modules that are directly related to the above reach settings.

The link labeled "MULT" on the board of the VMM115 module must be set to the same value selected for the rotary switch on the AFM133 module associated with M1/MG1 (located in position "Y"). The dip switch labeled "0(1) SUP" on the board of the AFM217 module must be set equal to 0.1/MULT, where MULT is the reach multiplier set on the front panel rotary switch of the AFM133 module associated with M1/MG1 (located in position "Y"). The dip switch labeled "0(T) SUP" must be set equal to 0.1/MULT, where MULT is the reach multiplier set on the front panel rotary switch of the AFM133 module associated with MT/MTG (located in position "S"). Both "0(1) SUP" and "0(T) SUP" have a setting range of 0.1 to 1.5, with a resolution of 0.03. The actual setting is equal to 0.1 plus the sum of the switch toggles set to the "right" position.

The overreaching functions are always used with the pilot channel to provide high-speed protection for faults anywhere on the transmission line. To this purpose, they must be set to reach beyond the remote terminal of the line. The overreaching functions should never be set less than 125% of the line impedance, but can be set longer than this to provide improved performance or to control timers (II and III) so that time-delayed backup tripping can be provided, independent of the pilot trip.

The first timer (II) can be used to provide zone 2 protection in conjunction with the zone 1 functions by extending

the zone 1 reach to zone 2 when this timer times out.

The second timer (III) works directly with the overreaching functions and can be used to:

- a. initiate zone 3 tripping if the zone 1 functions are used in the extendedreach mode to provide zone 2 backup.
- b. initiate zone 2 tripping if the zone 1 functions are not used in the extended-reach mode for 2nd zone backup.

Each timer is set or disabled using switches located on the front panel of the ULM234, Figure MO-11 in the MODULES section.

It follows from the above discussion that it is necessary to decide how many zones of backup protection are to be used in a particular application.

If it is acceptable to extend the reach of the 1st zone functions, up to three zones of protection can be provided:

- a. The 1st zone functions would be set to reach no more than 90% of the transmission line impedance. The zone 1 reach setting is made using switches located on the front panel of the AFM133 module (position Y), Figure MO-4.
- b. The zone 1 reach-extension factor would be set to give the desired 2nd zone reach. For example, a zone 2 reach equal to 125% of the protected line can be obtained with the reach-extension setting set as close as possible to 125/90 or 1.39. The reach extension setting is made using switches located on the front panel of the VMM11(-) module, Figure MO-13 in the MODULES section. The zone timer switch (II) labeled OUT on the ULM234 Module, figure MO-11, would be set to the left (IN) position.

Third (3rd) zone protection would be c. obtained by setting the overreaching functions (if possible) to reach beyond the remote terminal of any line that emanates from the bus at the remote terminal of the line to be protected. The reach setting is made using switches located on the front panel of the AFM133 module (position S), Figure MO-4. Zone timer III on the ULM234 Module, Figure MO-11, would be set to 3rd zone time, and its switch, labeled OUT, would be set to the left (IN) position. If 3rd zone backup protection is not required, set the zone timer III switch to the right (OUT) position and select a reach setting for the overreaching functions that is at least 10% larger than the selected 2nd zone reach.

If it is not acceptable to extend the 1st zone functions in reach, only two zones of protection can be provided:

- a. The 1st zone functions would be set to reach 90% of the transmission line impedance.
- b. The zone timer (II) switch would be set to the right (OUT) position.
- c. The overreaching functions would be set with a suitable 2nd zone reach, keeping in mind the 125% minimum-setting limitation proposed earlier. Set the zone timer switch (III) labeled OUT to the left (IN) position. If zone 2 backup protection is not desired, set the zone timer switch (III) to the right (OUT) position.

After a reach setting has been selected for the overreaching functions, it is desirable to check that the selected reach setting has not exceeded allowable limits. The maximum allowable reach setting that can be made is dependent on the impedance angle of the transmission line, the maximum load flow (minimum load impedance) across the line, and the characteristic shape selected for the distance functions. Three different characteristic shapes can be selected (see Figure CS-1 for details). Larger maximum




Figure CS-1 (0285A9991-1) Phase Distance Functions Characteristic Shapes

reaches can be used if the characteristic is made more lenticular, but at a slight increase in operating time because the characteristic timer setting must be increased to obtain the lenticular shape. To get the best possible operating time, a circular characteristic should be used whenever possible.


The maximum allowable reach setting can be easily calculated if the maximum load flow across the line is known. Please refer to Figure CS-2 for details.

The criterion used for establishing the maximum allowable reach is based on maintaining a 40° angular margin between the angle A and the characteristic angle B; i.e., B > A by 40°. With this margin maintained, the functions will be secure from operation as a result of load because the blocks created at the input to the characteristic timer (see Figure CS-1) due to load will be approximately 2 milliseconds less than the timer pickup setting.

Please note that the settings described above are predicated on using the overreaching functions as part of the stepped distance backup protection. If this function is not required as part of the backup, the best possible performance will be obtained from the pilot scheme if the reach of the overreaching functions is set as large as possible, but not larger than the maximum allowable reach described in equation (3) in Figure CS-2.

Ground Zone 1 Characteristic, Mho or Reactance

The ground zone 1 functions can be set to operate with a variable mho or reactance characteristic. When operated with a reactance characteristic, the function is supervised by the MTG overreaching functions. The reactance characteristic will provide more resistance coverage than will the variable mho, but slightly slower operating times will be



Where:

$$\begin{array}{lll} A = & 50 \text{ for circle } (B = 90) & C = \\ A = & 65 \text{ for lens } (B = 105) & D = \\ A = & 80 \text{ for lens } (B = 120) & \text{maximum reach; use next higher} \\ ZL = & |\text{Minimum load impedance} \\ & (\text{maximum load current})| & E = & |D-C| \end{array}$$

Figure CS-2 (0285A9992-1) Overreaching Function Load Coordination

experienced for zone 1 trips because of the necessity of the mho supervision.

Characteristic selection is made via three switches that are located on the board of the ETM111 module, Figure MO-9. The variable mho characteristic is selected when the switches are in the ON position. With the switches in the OFF position, the reactance characteristic is selected.

Directional supervision of the reactance characteristic is made via dip switch settings on the board of the UTM111 module, Figure MO-16.

When each of the $\emptyset A$, $\emptyset B$, and $\emptyset C$ "MG-1 SUP" switches are set to the "REACT" position, the zone 1 function is supervised by MTG. When the reactance

characteristic is selected on the ETM111 module, the "MG-1 SUP" switches must be When the mho set to REACT. characteristic is selected on the ETM111 module, the "MG-1 SUP" switches must be set to MHO.

WORKED EXAMPLE (distance tripping functions)

As an example of the settings to be made on the distance functions, consider the typical transmission line shown in Figure CS-3 and assume that three zones of protection are to be used in the TYS system located at Station Able. To accomplish this, the 1st zone functions will be increased in reach following zone 2 time to provide zone 2 protection, and, for 3rd zone protection, the overreaching functions will be set, if possible, to reach beyond the remote ends of




Figure CS-3 (0285A9993) Typical Transmission System

the lines emanating from Station Baker to Station Charlie and Station Delta.

Positive-Sequence Angle of Maximum Reach, ØZ1

Set the positive-sequence angle of maximum reach (ϕZ_1) to 85°, using the switch located on the front panel of the ISM11(-) module, Figure MO-10.

Zero-Sequence Angle of Maximum Reach, $\emptyset Z_0$

Set the zero-sequence angle of maximum reach $(\emptyset Z_0)$ to 75° using the switch located on the front panel of the ISM11(-) module, Figure MO-10.

MTG Zero-Sequence Current Compensation, K₀

From equation (1) above:

$$K_0 = 31.5/10 = 3.15$$

The nearest setting is 3.2. Set K0 for MTG to 3.2, using the switches located on the board of the AFM133 module (position S), Figure MO-4.

MG1 Zero-Sequence Current Compensation, K₀

From equation (2) above:

$$K_0 = (0.95 \times 31.5)/10 = 2.99$$

The nearest setting is 3.0. Set K_0 for MG1 to 3.0, using the switches located on the board of the AFM133 module (position Y), Figure MO-4.

M1 and MG1 Reach

Set the zone 1 functions to reach 90% of the positive-sequence impedance of the transmission line.

$$ZR1 = 0.9 \times 10 = 9 \text{ ohms}$$

Set "MULT" = 1, using the rotary switch on the front panel of the AFM133 module located in position "Y". Set "r" = 9 ohms, using the dip switches on the front panel of the same module. Set "MULT" = 1, using the link located on the board of the same module. Refer to Figure MO-4 for the locations of these settings. The reach of both M1 and MG1 is established with these settings.

Set "MULT" = 1, using the link located on the board of the VMM115 module. Set "O(1) SUP" = 0.1/1 = 0.1, using the switch on the board of the AFM217 module.

Second Zone Reach (extension factor), Timer II

Zone 2 protection will be provided by increasing the reach of the zone 1 functions (M1 and MG1) following a 2nd zone time delay set on timer II. The timer is started by

MB Reach

The reach of the blocking functions will be established using equation (5) above because the reach of the overreaching functions at Station Able (28.6 ohms) is greater than twice the positive-sequence impedance of the line:

MB Reach =
$$(28.6-10)\times1.7 = 31.6$$
 ohms

Set 31.6 ohms, using the "r" switches located on the front panel of the ABM11(-) module, Figure MO-2.

Zero-Sequence Current Compensation Factor, K

The MB zero-sequence compensation factor is calculated using equation (6) above:

$$K = \frac{(31.5 - 10)}{10} = 2.15$$

The nearest available setting is 2.2. Set 2.2, using the switches located on the board of the ABM11(-) module, Figure MO-2.

MB Characteristic Timer

Set the MB characteristic timers for 95°, using the switches located on the board of the UTM111 module, Figure MO-16.

OVERCURRENT FUNCTIONS

The following overcurrent functions must be set:

- IPB Pilot blocking (0.05-0.755 per unit, 0.025 step)
- Iøø MT overcurrent supervision (0.1-1.0 per unit, 0.1 step)
- IM Overcurrent supervision (0.05-0.755 per unit, 0.025 step)
- I1 Line pickup (0.2-3.2 per unit, 0.2 step)


IPB, Pilot Blocking

IPB uses zero-sequence current with positive-sequence restraint (I_0 - K_BI_1). It is used to supervise the NB function. The setting is made in per-unit current, where rated current, I_N , (1or 5 amperes) is used as the base, and it is actually in terms of $3x(I_0$ - K_BI_1). IPB should be set to its minimum setting of 0.05 per-unit current. The setting is made using the switches located on the board of the ADM112 module, Figure MO-3.

Iøø, MT Supervision

Iøø is not a separate overcurrent function but rather an input to the MT phase distance function comparator, however it acts just like an overcurrent function to establish trip level supervision of MT. Iøø uses delta current for the operating quantity (i.e., IA - IB for the ØA-B MT function), but its setting is based on phase current. The setting is made in perunit current, where rated current, I_N (1 or 5 amperes) is used as the base. Iøø must coordinate with IM at the remote terminal since IM provides overcurrent supervision of the MB blocking functions. For two terminal applications, Iøø should be set for its minimum value of 0.1 per-unit current. For three terminal applications, the coordination margin should be doubled by increasing the Iøø setting to 0.2. Both of these recommended settings are based on the IM setting suggested below. The setting is made using the switches located

For the balance of the text of the CALCULATION OF SETTINGS section, please refer to pages CS-8 - CS-13 of GEK-90658.








Figure MO-4 (0285A5469) Front Panels and Internal Switch, AFM13(-) Module




Figure MO-5 (0285A5470) Internal Switches and Links, AFM21(-) Module




Figure MO-13 (0285A5471) VMM115 Module

TABLE AT-I

| | | LINK/ | | |
|-------------|-------------------|-------------------|---------------------------------------|---|
| MODULE | T 0 0 1 m 1 0 1 1 | SWITCH | | |
| NAME | LOCATION | NAME | | SETTING |
| ABM11(-) | ZC · | K | (SWITCH) | 1.0 |
| 1 | | \mathbf{K}_{V} | (SWITCH) | 0.3 |
| | | $\overline{I_1}$ | (SWITCH) | 0.3 |
| A D34110 | | - | · · · · · · · · · · · · · · · · · · · | ~ |
| ADM112 | ZG | IPB BIAS | (SWITCH) | 0.05 |
| | | IM BIAS | (SWITCH) | 0.05 |
| AFM133† | Y | K0 | (SWITCH) | 4.0 |
| | | 110 | (BWIICII) | 4.0 |
| AFM133 | S | 0 SUP | (SWITCH) | 0.1 |
| | S | MULT | (LINKS) | 1.0 |
| AFM217 | U | O(I) SUP | (SWITCH) | 0.1 |
| 111 11121 | Ŭ | O(T) SUP | (SWITCH) | $\begin{array}{c} 0.1 \\ 0.1 \end{array}$ |
| | | 0(1) 501 | (DWIICII) | 0.1 |
| CTM12(-) | ZJ | IDT DIR. CONTROL | (LINK) | "IN" |
| | (OPTION) | ITOC DIR. CONTROL | (LINK) | "IN" |
| | | PT PU | (SWITCH) | 0.5 |
| ETM111 | W | PHA - VP | (SWITCH) | "ON" |
| | ** | PHB - VP | (SWITCH) | "ON" |
| | | PHC - VP | (SWITCH) | "ON" |
| | | | , , , , , , , , , , , , , , , , , , , | 011 |
| IOM112 | 2N | DC PWR SUP SOURCE | (LINK) | RATED |
| TAM101 | D | LOGIC VOLT | (LINK) | 12 VDC |
| | (OPTION) | SW4 | (SWITCH) | AS REQ'D |
| | | | (57711011) | AD ILLY D |
| ULM227 | K | TL1 | (SWITCH) | 0.0 |
| | | TL16 | (SWITCH) | 0.0 |
| UTM111 | M | MG1 | (SWITCH) | МНО |
| | 747 | MT | (SWITCH) | 90° |
| | | MTG | (SWITCH) | 90° |
| | | MOB | (SWITCH) | 12 4 ° |
| | | MB | (SWITCH) | 80° |
| | • | FREQ. | (SWITCH) | RATED |
| VMM115 | ZE | MULT | (LINK) | 1.0 |
| L 111111111 | <u> </u> | WOLL | (TIIIII) | 1.0 |

† Refer to the specific model number, the Nomenclature Selection Guide (INTRODUCTION section) and Table AT-II to determine which range has been supplied.

TABLE AT-II

| MODULE NAME | LOCATION | SWITCH NAME | SETTING | RANGE |
|------------------|----------|---|-------------------|--|
| ABM11(-) | ZC | r | 6.0 | (2 TO 50 Ω) |
| AFM133 AFM133 | Y Y | r MULT | 3.0 1.0 | $(0.2{ m TO}50\Omega) \ (0.1{ m TO}2.5\Omega)$ |
| CTM12(-) | ZJ | TOC PU TD IDT PU | 0.6 1.0 4.0 | (0.05 TO 0.6 PU) (0.5 TO 10) (0.4 TO 4.0 PU) |
| ETM114 | P | Iø - ø | 0.1 | (0.1 to 1.0 U) |
| ISM11(-) | ZA | $egin{array}{l} rak{	ilde{g}}\mathbf{Z}_{0} \ \end{array}$ | 85° 85° | (50 TO 85°) (50 TO 85°) |
| ULM234 | H | TIMER II TIMER III | 0.0 | (0 TO 3.1 SEC) (0 TO 3.1 SEC) |
| ULM258 | F | OSB-1 OSB-2 | OPEN OPEN | |
| VMM11(-) | ZE | II | 1.0 | (1 TO 10) ×ZONE 1 |

I1 Detector Test

1. With the connections as shown in Figure AT-1, move the oscilloscope input to card-extender Pin 24. Increase IOP until the oscilloscope trace goes from LOW to HIGH. At this point the current should be between 2.9 (0.59) and 3.3 (0.66) amperes rms.

V1 DETECTOR TEST

- With the connections as shown in Figure AT-2, move the oscilloscope input to card-extender Pin 26. Set angle VA = 0°, VB = -120° and VC = +120° or -240°. Set voltage VA, VB and VC to 67 volts rms.
- 2. Reduce the three-phase voltage, simultaneously, until the oscilloscope trace goes from LOW to HIGH. At this point the voltage should be between 48.5 and 51.5 volts rms.

NEGATIVE-SEQUENCE DIRECTIONAL TESTS

NT Test

- With the connections as shown in Figure AT-3, move the oscilloscope input to card-extender Pin 18. Connect the relay input "Y" to BH1 (TP9 for post-installation testing). Set angle VA=0°, VB=-120° and VC=+120° or -240°. Set voltage VA, VB and VC to 67 volts rms.
- 2. Set angle $I_{OP} = -85^{\circ}$. Reduce voltage VA to 30 volts rms and slowly increase I_{OP} until the trace on the scope goes from LOW to HIGH. At this point current I_{OP} should be less than 1.0 ampere rms.
- 3. Change angle I_{OP} to +95° and check that the oscilloscope trace does not go HIGH as I_{OP} is increased up to 10 (2) amperes rms.

NB Test

- 1. With the angle I_{OP} set to +95°, move the oscilloscope input to card-extender Pin 14. Reduce I_{OP} to 1.0 (0.2) amperes rms and check that the oscilloscope trace is HIGH.
- 2. Change angle IOP to -85° and check that the oscilloscope trace is LOW.

REACH TESTS

M1 Test

With the connections as shown in Figure AT-4 for the appropriate phases and function to be tested, set angle VA=0°, VB=-120° and VC=+120° or -240°. Set voltage VA, VB and VC to 67 volts rms. Set the phase angle of Iop to the values indicated in Table AT-III.

TABLE AT-III

| Volts RMS | I Degrees |
|-----------|-----------|
| 26 - 30 | -25 |
| 32 - 37 | -55 |
| 26 - 30 | -85 |

2. Set IOP to 10 (2) amperes rms. Simultaneously reduce the voltage of the faulted phases and check that the appropriate pin on the card extender goes from LOW to HIGH within the voltage limits given in Table AT-III.

MT Tests

- 1. With the connections as shown in Figure AT-4 for the appropriate phases and function to be tested, set angle $VA=0^{\circ}$, $VB=-120^{\circ}$ and $VC=+120^{\circ}$ or -240° . Set voltage VA, VB and VC to 67 volts rms. Set the phase angle of Iop to the values indicated in Table AT-IV.
- 2. Set IOP to 10 (2) amperes rms. Simultaneously reduce the voltage of the faulted phases and check that the appropriate pin on the card extender

TABLE AT-IV

| Volts RMS | I Degrees |
|-----------|----------------|
| 26 - 30 | -25 |
| 32 - 37 | 55 |
| 26 - 30 | -85 |

goes from LOW to HIGH within the voltage limits given in Table AT-IV.

MG1 Tests

1. With the connections as shown in Figure AT-6 for the appropriate phase and function to be tested, set angle $VA=0^{\circ}$, $VB=-120^{\circ}$ and $VC=+120^{\circ}$ or -240° . Set voltage VA, VB and VC to 67 volts rms. Set the phase angle of I_{OP} to the values indicated in Table AT-V.

TABLE AT-V

| I Degrees |
|-----------|
| -55 |
| -85 |
| -115 |
| |

2. Set Iop to 7.5 (1.5) amperes rms. Reduce the voltage of the faulted phase and check that the appropriate pin on the card extender goes from LOW to HIGH within the voltage limits given in Table AT-V.

MTG Tests

- 1. With the connections as shown in Figure AT-6, for the appropriate phase and function to be tested, set angle $VA=0^{\circ}$, $VB=-120^{\circ}$ and $VC=+120^{\circ}$ or -240° . Set voltage VA, VB and VC to 67 volts rms. Set the phase angle of I_{OP} to the values indicated in Table AT-VI.
- Set I_{OP} to 7.5 (1.5) amperes rms. Reduce the voltage of the faulted phase and check that the appropriate pin on the card extender goes from LOW to HIGH within the voltage limits given in Table AT-VI.

TABLE AT-VI

| Volts RMS | I Degrees |
|-----------|------------|
| 34 - 39 | -55 |
| 40 - 47 | -85 |
| 34 - 39 | -115 |

MB Tests

1. With the connections as shown in Figure AT-3 for the appropriate phase to be tested, set angle VA = 0°, VB = -120° and VC = +120° or -240°. Set voltage VA, VB and VC to 67 volts rms. Set the phase angle of IOP to the values indicated in Table AT-VII.

TABLE AT-VII

| \ | olts RMS | I Degrees |
|---|----------|-----------|
| - | 50 - 58 | +65 |
| | 52 - 60 | +95 |
| | 50 - 58 | +125 |
| 1 | | |

2. Set IOP to 5 (1) amperes rms. Simultaneously reduce the three-phase voltage and check that the appropriate pin on the card extender goes from LOW to HIGH within the voltage limits given in Table AT-VII.

MOB Tests

- 1. Change the MOB timer setting to 60°. This is accomplished by means of a switch located on the board of the UTM111 module, Figure MO-16, which is found in location "M".
- 2. With the connections as shown in Figure AT-8, connect the oscilloscope input to card-extender Pin 27. Set angle $VA = 0^{\circ}$, $VB = -120^{\circ}$ and $VC = +120^{\circ}$ or -240° . Set voltage VA, VB and VC to 67 volts rms. Set the phase angle of I_{OP} to the values indicated in Table AT-VIII.
- 3. Set IOP to 10 (2) amperes rms. Simultaneously reduce the voltage of the faulted phases until the trace on the oscilloscope, Pin 27, goes from LOW to HIGH (First Pulse) within the voltage

TABLE AT-VIII

| Volts RMS | I Degrees |
|-----------|------------|
| 35 - 41 | –25 |
| 35 - 41 | 85 |
| | |

limits given in Table AT-VIII. Move the oscilloscope input to card-extender Pin 45 and check that it also has changed from LOW to HIGH.

- 4. Connect the oscilloscope input to cardextender Pin 8, 9 or 10, determined by the phases that are being tested. Continue to reduce the voltage of the faulted phases until the trace on the oscilloscope goes from LOW to HIGH. Also, check that the trace on the oscilloscope from card-extender Pin 45 remained HIGH.
- 5. Increase the voltage of the faulted phases back to 67 volts rms and check that the trace on the oscilloscope from card-extender Pin 45 returned to a LOW.
- 6. Reset the MOB timer to its pre-test position. (See Table AT-I)

SETTINGS LIST A (Blank Form) TYS3 PHASE AND GROUND DISTANCE PERMISSIVE SCHEME SETTING LIST

| Mod Loca Z | tion | Module ABM11(-) ABM11(-) ABM11(-) ABM11(-) | Adjustment I ₁ KV K | Description Line PU supervision Pos. seq. volt. comp. MB zero seq. curr. comp. | on board on board on board | Setting 0 |
|------------------|------|--|--|---|---|--------------|
| Z | G | ADM112 ADM112 | r IM BIAS IPB BIAS | MB reach setting Overcurrent supervision Pilot blocking | on board on board | 0.05 |
| Y | | AFM133 AFM133 AFM133 AFM133 | r MULT MULT KO | Zone 1 reach (M1/MG1) Reach multiplier Clip level Zero seq.curr.comp(M1/MG1) | front panel front panel on board on board | |
| S | | AFM133 AFM133 AFM133 AFM133 | r MULT MULT K0 | Overreaching (MT/MTG) reach Reach multiplier Clip level Zero seq.curr.comp(MT/MTG) | front panel front panel on board on board | |
| U | Ţ | AFM217 AFM217 | 0(1) SUP 0(T) SUP | Zone 1: zero suppression Zone 2: zero suppression | on board on board | |
| V | | ETM111 ETM111 ETM111 | PHA - VP PHB - VP PHC - VP | MG1 Characteristic REACTANCE = OFF MHO = ON | on board on board on board | |
| P | • | ETM114 | Iøø | MT overcurrent supervision | front panel | |
| Z | N | IOM112 | VDC | Contact conv. volt. | on board | |
| Z | A | ISM11(-) ISM11(-) | $ ^{\not o}_{z_0}^{z_1}$ | Pos. seq. reach ang. Zer. seq. reach ang. | front panel front panel | |
| K | ζ. | ULM227 | TL1 | Trip integrator | on board | |
| F | I | ULM234 ULM234 | TIMER II TIMER III | Zone() timer Zone() timer | front panel front panel | |
| F | י | ULM258 ULM258 | OSB-1 OSB-2 | OSB option OSB option | front panel front panel | |
| Ŋ | M. | UTM111 UTM111 UTM111 UTM111 UTM111 | MT MTG MB MOB MG1-SUP | MT char. timer MTG char. timer MB char. timer MOB char. timer MG1 supervision | on board on board on board on board on board | |
| 7 | ZE | VMM115 VMM115 | II MULT | Zone 1 ext. factor Zero suppression | front panel on board | |
| _ | | | unctions (when inc | | | |
| 2 | ZJ | CTM12(-) CTM12(-) CTM12(-) CTM12(-) CTM12(-) CTM12(-) | TD TOC PU DT PU PT PU ITOC DIR CON IDT DIR CONT | | front panel front panel front panel on board on board on board | |

SETTINGS LIST B (Worked Example) TYS3 PHASE AND GROUND DISTANCE PERMISSIVE SCHEME SETTING LIST

| Modula | | | | 0 |
|--------|--|---|---|---|
| ZC | ABM11(-) ABM11(-) ABM11(-) ABM11(-) ABM11(-) | Adjustment I1 KV K r | Description Line PU supervision Pos. seq. volt. comp. MB zero seq. curr. comp. MB reach setting | $ \begin{array}{c c} \textbf{Switch} \\ \underline{\textbf{Location}} & \underline{\textbf{Setting}} \\ \textbf{on board} & \underline{\textbf{0.6}} \\ \textbf{on board} & \underline{\textbf{0}} \\ \textbf{on board} & \underline{2.2} \\ \textbf{front panel} & \underline{31.6\Omega} \\ \end{array} $ |
| ZG | ADM112 ADM112 | IM BIAS IPB BIAS | Overcurrent supervision Pilot blocking | on board 0.05 on board 0.05 |
| Y | AFM133 AFM133 AFM133 AFM133 | r MULT MULT K0 | Zone 1 reach (M1/MG1) Reach multiplier Clip level Zero seq.curr.comp(M1/MG1) | $\begin{array}{c} \text{front panel} & \underline{9\Omega} \\ \text{front panel} & \underline{1} \\ \text{on board} & \underline{1} \\ \text{on board} & \underline{3.0} \end{array}$ |
| S | AFM133 AFM133 AFM133 AFM133 | r MULT MULT K0 | Overreaching (MT/MTG) reach Reach multiplier Clip level Zero seq.curr.comp(MT/MTG) | front panel $\frac{28.6\Omega}{l}$ front panel $\frac{l}{l}$ on board $\frac{l}{3.2}$ |
| U | AFM217 AFM217 | 0(1) SUP 0(T) SUP | Zone 1: zero suppression Zone 2: zero suppression | on board 0.1 on board 0.1 |
| W | ETM111 ETM111 ETM111 | PHA - VP PHB - VP PHC - VP | REACTANCE = OFF | on board MHO (ON) on board MHO (ON) on board MHO (ON) |
| P | ETM114 | Iøø | MT overcurrent supervision | front panel 0.1 |
| ZN | IOM112 | VDC | Contact conv. volt. | on board <u>125VDC</u> |
| ZA | ISM11(-) ISM11(-) | $m{f g}{f Z}_1 \ m{f g}{f Z}_0$ | Pos. seq. reach ang. Zer. seq. reach ang. | front panel $\frac{85^{\circ}}{75^{\circ}}$ |
| K | ULM227 | TL1 | Trip integrator | on board 4.0 ms |
| Н | ULM234 ULM234 | TIMER II TIMER III | Zone() Timer Zone() Timer | front panel $\frac{0.2 \text{ sec}}{0.5 \text{ sec}}$ |
| F | ULM258 ULM258 | OSB-1 OSB-2 | OSB option OSB option | front panel IN front panel IN |
| M | UTM111 UTM111 UTM111 UTM111 UTM111 | MT MTG MB MOB MG1-SUP | MT char. timer MTG char. timer MB char. timer MOB char. timer MG1 supervision | on board $\frac{105^{\circ}}{95^{\circ}}$ |
| ZE | VMM115 VMM115 | II MULT | Zone 1 ext. factor Zero suppression | front panel $\frac{1.4}{1}$ on board |
| Option | al overcurrent f | unctions (when inc | luded) | |
| ZJ | CTM12(-) CTM12(-) CTM12(-) CTM12(-) CTM12(-) CTM12(-) | TD TOC PU DT PU PT PU ITOC DIR CON IDT DIR CON | TOC time dial TOC pickup IDT pickup IPT pickup TOC directional cont. IDT directional cont. | $\begin{array}{c} \text{front panel} & \underline{2.0} \\ \text{front panel} & \underline{0.05} \\ \text{front panel} & \underline{0.7} \\ \text{on board} & \underline{0.1} \\ \text{on board} & \underline{IN} \\ \text{on board} & \underline{OUT} \\ \end{array}$ |

the operation of the MT overreaching functions. Assume that zone 2 reach is to be 125% of the protected line, and that a zone 2 time of 0.2 seconds is required.

$$Z_2 = 1.25 \times 10 = 12.5 \text{ ohms}$$

Reach Extension Factor
$$=\frac{Z2}{Z1} = \frac{12.5}{9}$$

= 1.39

The nearest available setting for the reach multiplier is 1.40. Set 1.4, using switches located on the front panel of the VMM115 module, Figure MO-13.

Set the 0.2-second Zone 2 time delay and set the timer switch labeled OUT, to the left (IN) position, using the switches marked TIMER II and located on the front panel of the ULM234 module, Figure MO-11.

MT and MTG Reach (Overreaching) and Characteristic Shape, Timer III

If the MT and MTG overreaching functions are to reach beyond the remote terminals of the lines emanating from Station Baker, the effects of infeed at Station Baker must be taken into account in establishing a reach setting. Fault studies were run with and without load flow for the system shown in Figure CS-3, and it was established that the maximum apparent impedance seen by the relays at Station Able was:

Z = 22.9 ohms, for a single-line-toground fault at Station Charlie (no load)

The studies showed that the apparent impedance seen with load flow was less than the value given above.

It is proposed that the MT overreaching functions be set with a reach that is 25% greater than the maximum apparent impedance seen by the functions, and that timer III be set to pick up in 3rd zone time of 0.5 seconds.

 $ZRT = 1.25 \times 22.9 = 28.6 \text{ ohms.}$

It is next necessary to check the maximum allowable reaches that are permitted for the conditions given in Figure CS-3. From equation (3) above and from the system data given in Figure CS-3, the following maximum reaches can be calculated (use a relay angle of maximum reach of 85°):

MR = 21.9 ohms with 90° circle MR = 32.8 ohms with 105° lens MR = 50 ohms (maximum available) with 120° lens

To obtain the reach of 28.6 ohms calculated above, the overreaching functions must be set with a 105° lens characteristic. Set "MULT" = 1, using the rotary switch on the front panel of the AFM133 module located in position "S". Set "r" = 28.6 ohms, using the dip switches on the front panel of the same module, and "MULT" = 1, using the link located on the board of the same module. Refer to Figure MO-4 for the locations of these settings. The reach of both MT and MTG is established with these settings.

Set "0(T) SUP" = 0.1/1 = 0.1, using the switch on the board of the AFM217 module.

Set the 105° lens characteristic for MT and MTG, using the respective switches located on the board of the UTM111 module, Figure MO-16.

Set the 3rd zone timer to 0.5 second, and set the timer switch, labeled OUT to the left (IN) position, using the switches marked TIMER III and located on the front panel of the ULM234 module, Figure MO-11.

Note: if 3rd zone protection is not required, the overreaching functions can be set with a circular (90°) characteristic, but the reach must be reduced to 21.9 ohms.

Ground Zone 1 (MG1) Characteristic

The variable mho characteristic will be used for the zone 1 ground distance functions in this application.

Select the mho characteristic, using the switches located on the board of the ETM111 module, Figure MO-7.

Select the mho supervision, using the switch located on the board of the UTM111 module, Figure MO-16.

Distance Function Sensitivity

If required, the sensitivity of the distance functions can be found using the calculated settings and the procedures defined in the SPECIFICATIONS section of this instruction book.

REVERSE-REACHING BLOCKING FUNCTIONS, MB

The following settings must be made:

a. MB Reach $(2\Omega-50\Omega, 0.2\Omega \text{ step})$

b. Zero-sequence current compensation, K (1-7, 0.1 step)

c. Characteristic timer setting (80°, 95°, 110°)

d. Positive-sequence voltage compensation, KV (0-0.3, 0.15 step)

MB Reach

The reach of the reverse-reaching blocking functions is dependent on the reach of the overreaching functions at the remote end of the line. The following settings are proposed:

a. If the MT reach at the remote terminal is less than twice the positive-sequence impedance of the line.

MB Reach = (MT reach)
$$\times 0.85$$
 (4)

b. If the MT reach at the remote terminal is greater than twice the positive-sequence impedance of the line.

MB Reach = $(MT \text{ reach } - Z_{1L}) \times 1.7$ (5)

Where: Z_{1L} = positive-sequence impedance of line.

The MB reach is set using the switches located on the front panel of the ABM11(-) module, Figure MO-2.

Zero-Sequence Current Compensation Factor, K

The zero-sequence current compensation factor, K, is a function of the positive- and zero-sequence impedances of the transmission line to be protected:

$$K = (Z_{0L} - Z_{1L})/Z_{1L}$$
 (6)

Where:

 Z_{0L} = zero-sequence impedance of line.

 Z_{1L} = positive-sequence impedance of line.

The MB zero-sequence current compensation factor is set using the switches located on the board of the ABM11(-) module, Figure MO-2.

MB Characteristic Timer Setting

The characteristic timer settings for the blocking functions should be set 10° less than the characteristic timer setting of the overreaching functions at the remote terminal of the line. The characteristic timer setting is made using the switches located on the board of the UTM111 module, Figure MO-16.

Positive-Sequence Voltage Compensation Factor, KV

The positive-sequence voltage compensation factor, KV, should be set to zero (0). The setting is made using the switches located on the board of the ABM11(-) module, Figure MO-2.

WORKED EXAMPLE (distance blocking functions)

The system of Figure CS-3 will be used. The blocking functions at Station Baker will be set to coordinate with the settings selected above for the overreaching functions at Station Able.

tolerance given in Table PT-I for the particular value of test current.

$$I = "I1" PU \times I_N \times 3 \tag{6}$$

WHERE:

"I1" PU is the per-unit setting on the board of the ABM11(-) module, Figure MO-2 IN is the rated relay current (1 or 5 amperes) I is the nominal pickup current

FD

The fault detector may be tested using the same method as specified under ACCEPTANCE TESTING since there are no customer settings on this function.

REACH TESTS

M1

Use the connections shown in Figure AT-4 for the appropriate phases and function to be tested.

Set the current and voltage phase angles per Table PT-II.

TABLE PT-II

| Phase AB Phase BC Phase CA | IOP | $-(\theta - 30)^{\circ}$ $-(\theta + 90)^{\circ}$ $(150 - \theta)^{\circ}$ |
|--|-----|--|
| V _A V _B V _C | | 0° -120° +120° |

Where: θ is the setting of " ϕZ_1 " on the front panel of the ISM11(-) module, Figure MO-9

The recommended test currents for this test are given in Table PT-III.

The nominal operating voltage for M1, at the angle of maximum reach, is given in Equation 7.

$$V_{NOM} = \frac{ZR1 \times 2 \times I_{TEST}}{\sqrt{3}}$$
 (7)

WHERE:

VNOM is the phase-to-ground pickup voltage
ITEST is the test current
ZR1 is the reach setting "r" times the multiplier setting "MULT" found on the front panel of the AFM133 module, Figure MO-4, found in location "Y"

TABLE PT-III

| т_ | F |
|--|--------------------------|
| $I_N = \frac{I_N}{ZR1 \text{ or "r"}(\Omega)}$ | I _{TEST} (amps) |
| 0.2 - 2.5 | 10 |
| 1 - 6 | 10 |
| 6 - 12 | 5 |
| 12 - 20 | . 3 |
| 20 - 25 | 2 |
| 25 - 50 | 1 |
| | |
| I_N : | |
| $ZR1 \text{ or "r"}(\Omega)$ | I _{TEST} (amps) |
| 0.5 - 125† | 2 |
| 5 - 30 | 2 |
| 30 - 60 | 1 |
| 60 - 100 | 0.6 |
| 100 - 125 | 0.4 |
| 125 250 | 0.2 |

NOTE: The switch marked "II" mounted on the front panel of the VMM11(-) module, Figure MO-13, should be set to 1 (all switches to left) when testing the M1 function.

The applied three-phase voltage should be initially set to a value greater than the nominal operating voltage and the current should be increased slowly to the recommended test value. The voltage of the faulted phases should be slowly lowered, simultaneously, until the trace on the oscilloscope steps from LOW to HIGH. The actual operating voltage should be within the tolerances given in Table PT-I for the value of test current used.

To check the M1 function at other angles, refer to the TYSTEST computer program provided in the SOFTWARE section of this manual.

MT

Use the connections shown in Figure AT-4 for the appropriate phases and function to be tested.

Set the current and voltage phase angles per Table PT-II.

The recommended test currents for this test are given in Table PT-IV.

TABLE PT-IV

| $I_N =$ | 5 |
|------------------------|--------------------------|
| ZRT or "r" (Ω) | I _{TEST} (amps) |
| 0.2 - 2.5 | 10 |
| 1 - 6 | 10 |
| 6 - 12 | 5 |
| 12 - 20 | 3 |
| 20 - 25 | 2 |
| 25 - 50 | 1 |
| | |
| $I_N =$ | |
| ZRT or "r"(Ω) | ITEST(amps) |
| 0.5 - 125 | 2 |
| 5 - 30 | 2 |
| 30 - 60 | 1 |
| 60 - 100 | 0.6 |
| 100 - 125 | 0.4 |
| 125 250 | 0.2 |

The nominal operating voltage for MT, at the angle of maximum reach, is given in Equation 8.

$$V_{NOM} = \frac{ZRT \times 2 \times I_{TEST}}{\sqrt{3}}$$
 (8)

WHERE:

V_{NOM} is the phase-to-ground pickup voltage I_{TEST} is the test current ZRT is the reach setting "r" times the multiplier setting "MULT" found on the front panel of the AFM133 module, Figure MO-4, found in location "S".

The applied three-phase voltage should be initially set to a value greater than the nominal operating voltage and the current should be increased slowly to the recommended test value. The voltage of the faulted phases should be slowly lowered, simultaneously, until the trace on the oscilloscope steps from LOW to HIGH. The actual operating voltage should be within the tolerances given in Table PT-I for the value of test current used.

To check the MT function at other angles, refer to the TYSTEST computer program provided in the SOFTWARE section of this manual.

MG1

Use the connections shown in Figure AT-6, for the appropriate phase and function to be tested.

Set the current and voltage phase angles per TABLE PT-V.

TABLE PT-V

| Phase AN I _{OP} Phase BN I _{OP} Phase CN I _{OP} | $-(\theta)^{\circ}$ $-(\theta + 120)^{\circ}$ $(120 - \theta)^{\circ}$ |
|--|--|
| V _A | 0° |
| V _B | -120° |
| V _C | +120° |

Where θ , the phase angle of I_{OP} , is determined by the following expression:

$$ZG = \left[r\right] \times \left[\left(\frac{2}{3}\right) \angle \emptyset Z_1 + \left(\frac{K_0}{3}\right) \angle \emptyset Z_0\right]$$

$$ZG = \left|ZG\right| \angle \theta \tag{9}$$

WHERE:

ØZ₁ is the positive-sequence impedance characteristic angle setting, found on the front panel of the ISM11(-) module, Figure MO-10

ØZ₀ is the zero-sequence impedance characteristic angle setting, found on the front panel of the ISM11(-) module

"r" is the nameplate reach setting (located on the front panel of the AFM13(-) module, Figure MO-4, and found in location "Y") times the multiplier setting "MULT"

K₀ is the zero-sequence current compensation factor, found on the board of the AFM133 module, location "Y"

The nominal operating voltage for MG1, at the angle of maximum reach is given in Equation 10.

$$V_{NOM} = I_{TEST} \times |ZG|$$
 (10)

WHERE: V_{NOM} is the phase-to-ground pickup voltage
I_{TEST} is the test current
ZG is the reach as determined above (equation 9)

NOTE: The switch marked "II", mounted on the front panel of the VMM11(-) module, Figure MO-13, should be set to 1 (all switches to left) when testing the MG1 function.

The applied three-phase voltage should be initially set to a value greater than the nominal operating voltage and the current should be increased slowly to the recommended test value shown in Table PT-VI. The voltage of the faulted phase should be slowly lowered, until the trace on the oscilloscope steps from LOW to HIGH. The actual operating voltage should be within the tolerances given in TABLE PT-I for the value of test current used.

NOTE: The test currents indicated in Table PT-VI should only be used as guidelines. The maximum amount of test current that can be applied to obtain a favorable test result is determined by several factors, e.g. MG1 reach setting, K₀ setting, etc. Therefore, to make certain that the maximum allowable test current has not been exceeded, refer to the TYSTEST computer program furnished in the SOFTWARE section of this manual.

To check the MG1 function at other angles, refer to the TYSTEST computer

TABLE PT-VI

| $I_{N} = \frac{1}{2R1 \text{ or "r"}(\Omega)}$ | 5 I _{TEST} (amps) |
|---|------------------------------------|
| $\begin{array}{cccc} 0.1 - & 2.5 \\ 1 & - & 6 \\ 6 & - & 12 \\ 12 & - & 20 \\ 20 & - & 25 \\ 25 & - & 50 \end{array}$ | 10 10 5 3 2 |
| $\frac{I_{N}}{ZR1 \text{ or "r"}(\Omega)} =$ | : 1 I _{TEST} (amps) |
| 0.5 - 12.5 5 - 30 30 - 60 60 - 100 100 - 125 125 - 250 | - 2 2 1 0.6 0.4 0.2 |

program provided in the SOFTWARE section of this manual.

MTG

Use the connections shown in Figure AT-6, for the appropriate phase and function to be tested.

Set the current and voltage phase angles per TABLE PT-V, where θ , the phase angle of IOP, is determined by the following expression:

$$ZG = \left[r\right] \times \left[\left(\frac{2}{3}\right) \angle \emptyset Z_1 + \left(\frac{K_0}{3}\right) \angle \emptyset Z_0\right]$$

$$ZG = \left|ZG\right| \angle \theta \tag{11}$$

WHERE:

øZ₁ is the positive-sequence impedance characteristic angle setting, found on the front panel of the ISM11(-) module, Figure MO-10

"r" is the nameplate reach setting, (located on the front panel of the AFM133 module,

Figure MO-5, found in location "S") times the multiplier setting "MULT"

K₀ is the zero-sequence current compensation factor, found on the board of the AFM133 module, location "S"

The nominal operating voltage for MTG, at the angle of maximum reach, is given in Equation 12.

$$V_{NOM} = I_{TEST} \times |ZG|$$
 (12)

WHERE:

V_{NOM} is the phase-to-ground pickup voltage
I_{TEST} is the test current
ZG is the reach as determined above (Equation 11)

The applied three-phase voltage should be initially set to a value greater than the nominal operating voltage and the current should be increased slowly to the recommended test value shown in Table PT-VII. The voltage of the faulted phase should be slowly lowered, until the trace on the oscilloscope steps from LOW to HIGH. The actual operating voltage should be within the tolerances given in TABLE PT-I for the value of test current used.

TABLE PT-VII

| $I_{N} = 5$ $ZRT \text{ or "r"}(\Omega)$ | | |
|--|------------------------------------|--|
| $\begin{array}{ccccc} 0.1 - & 2.5 \\ 1 & - & 6 \\ 6 & - & 12 \\ 12 & - & 20 \\ 20 & - & 25 \\ 25 & - & 50 \end{array}$ | 10 10 5 3 2 | |
| $I_{N} = 1$ $ZRT \text{ or "r"}(\Omega) \qquad I_{TEST}(amps)$ | | |
| 0.5 - 12.5 5 - 30 30 - 60 60 - 100 100 - 125 125 - 250 | - 2 2 1 0.6 0.4 0.2 | |

NOTE: The test currents indicated in Table PT-VII should only be used as guidelines. The maximum amount of test current that can be applied to obtain a favorable test result is determined by several factors, e.g. MTG reach setting, K₀ setting, etc. Therefore, to make certain that the maximum allowable test current has not been exceeded, refer to the TYSTEST computer program furnished in the SOFTWARE section of this manual.

To check the MTG function at other angles, refer to the TYSTEST computer program provided in the SOFTWARE section of this manual.

MB

Use the connections shown in Figure AT-3 for the appropriate phase to be tested.

Set the current and voltage phase angles per Table PT-VIII.

TABLE PT-VIII

| Phase B | IOP Lag by | 360 - (\theta B + 180) \cdot 120 - [360 - (\theta B + 180)] \cdot [360 - (\theta B + 180)] + 120 \cdot |
|--|------------|--|
| V _A V _B V _C | | 0° -120° +120° |

Where θB , the phase angle of I_{OP} , is determined by the following expression:

$$ZB = \left(\frac{r}{1 - K_{v}}\right) \times \left[\left(1 + \frac{0.1 \times K_{v}}{3}\right) \angle \emptyset Z_{1} + \left(\frac{K}{3}\right) \angle \emptyset Z_{0}\right]$$

$$ZB = |ZB| \angle \theta B \qquad (13)$$

WHERE:

 $\emptyset Z_1$ is the positive-sequence impedance characteristic angle setting, found on the front panel of the ISM11(-) module, Figure MO-10. $\emptyset Z_0$ is the zero-sequence impedance characteristic angle setting, found on the front panel of the ISM11(-) module.

"r" is the nameplate reach setting located on the front panel of the ABM11(-) module, Figure MO-2.

K is the zero-sequence current compensation factor, found on the board of the ABM11(-) module.

Ky is the positive-sequence voltage compensation factor, found on the board of the ABM11(-) module.

The nominal operating voltage for MB, at the angle of maximum reach in the blocking direction $(\theta B + 180^{\circ})$, is given in Equation 14.

$$V_{NOM} = I_{TEST} \times |ZB|$$
 (14)

WHERE:

V_{NOM} is the phase-to-ground pickup voltage
I_{TEST} is the test current
ZB is the reach in the blocking direction, as determined above (Equation 13)

Set voltage VA, VB and VC to 67 volts rms. Set the current to the value shown in Table PT-IV. Simultaneously reduce the three-phase voltage, and check that the appropriate pin on the card extender goes from LOW to HIGH. The actual operating voltage should be within the tolerances given in Table PT-I for the value of test current used.

NOTE: The test currents indicated in Table PT-IV should only be used as guidelines. The maximum amount of test current that can be applied to obtain a favorable test result is determined by several factors, e.g. MB reach setting, K setting, Kv setting, etc. Therefore, to make certain that the maximum allowable test current has not been exceeded, refer to the TYSTEST computer program furnished in the SOFTWARE section of this manual.

To check the MB function at other angles, refer to the TYSTEST computer

program provided in the SOFTWARE section of this manual.

MOB

The MOB function can be tested with specific settings for a particular application by the same method as specified under ACCEPTANCE TESTING. To determine the required values for Table AT-XIV, refer to the TYSTEST computer program provided in the SOFTWARE section of this manual.




Figure SE-1 (0215B8420 Sh.1) Measuring Functions Block Diagram




Figure SE-1 (0215B8420 Sh.2) Measuring Functions Block Diagram




Figure SE-1 (0215B8420 Sh.3) Measuring Functions Block Diagram




Figure SE-1 (0215B8420 Sh.4) Measuring Functions Block Diagram




Figure SE-1 (0215B8420 Sh.5) Measuring Functions Block Diagram




Figure SE-1 (0215B8420 Sh.6) Measuring Functions Block Diagram




Figure SE-1 (0215B8420 Sh.7) Measuring Functions Block Diagram

SPECIFICATIONS

CONTACT DATA

Continuous rating = 3 amperes
Make and carry for tripping duty:
(per ANSI C37.90) = 30 amps
Break 180 VA resistive at 125/250 VDC **Trip Outputs**

Break 60 VA inductive at 125/250 VDC

Thyristor Outputs Same as trip contacts except no

interrupting rating

Auxiliary Outputs Continuous rating = 3 amperes (including Alarms) Make and carry for 30 seconds =

5 amperes

Break 25 watts inductive at 125/250 VDC

Make and Carry continuously 50 watts Maximum of 250 volts or 0.5 ampere

DLA and Channel 10 watts

Control Contacts 250 VDC maximum, 0.5 amp maximum

REACH-SETTING RANGES

TABLE P-I

| FUNCTION | MEASURIN UNIT | G MULT | RANGE IN I _N = 5 | OHMS I _N =1 | | LUTION I _N =1 |
|----------|------------------|-----------|--------------------------------|---------------------------|------|-----------------------------|
| Zone 1 | M1 | 0.1 | 0.2 to 5.0 | 1.0 to 5.0 | 0.02 | 0.1 |
| | M1 | 0.25 | 0.5 to 12.5 | 2.5 to 62.5 | 0.05 | 0.25 |
| | M1 | 1.0 | 2.0 to 50 | 10 to 250 | 0.2 | 1.0 |
| Zone 2 | MT | 0.1 | 0.2 to 5.0 | 1.0 to 5.0 | 0.02 | 0.1 |
| | MT | 0.25 | 0.5 to 12.5 | 2.5 to 62.5 | 0.05 | 0.25 |
| | MT | 1.0 | 2.0 to 50 | 10 to 250 | 0.2 | 0.5 |
| Blocking | MB | | 2.0 to 50 | 10 to 250 | 0.2 | 1. |

REACH EXTENSION FACTOR

TABLE SP-II

| FUNCTION , | MEASURING UNIT | RANGE | RESOLUTION | |
|------------|----------------|-------------------|------------|--|
| Zone 1 | M1 | (1 - 10) × Zone 1 | 0.05 | |

EXAMPLE:

$$Z_{R1} = 3$$

$$RM = 1$$

$$\mathbf{R}\mathbf{\tilde{M}} = \mathbf{I}$$

$$X = 0.95; (1 - X) = 0.05 (5\% \text{ pull back})$$

$$I_{A}-I_{B} = \frac{(.905)}{(.05)(3)} = 6.03$$

$$I_{A}-I_{B} = 2I_{A} = 6.03$$

 $I_{A} = 3.015$

$$I_{A}$$
- $I_{B} = \sqrt{3} I_{A} = 6.03$
 $I_{A} = 3.48$

The current sensitivity for the ground distance units is determined from:

$$(I_{\theta} - I_{0}) Z_{R1} + I_{0} K_{0} Z_{R0} = \frac{(0.905) (RM)}{(1 - X)}$$

To use this formula, the ratio of I_0 to I_θ must be known or assumed.

WHERE: I_{θ}

is the phase current at relay

is the zero-sequence current at relay $\mathbf{z}_{\mathbf{R}_1}$ is the positive-sequence relay reach

is the zero-sequence relay reach

 $(\mathbf{Z}_{\mathbf{R}\mathbf{1}} = \mathbf{\bar{Z}}_{\mathbf{R}\mathbf{0}})$

is the zero-sequence current compensation factor $\mathbf{K_0}$

is a design constant (see Table SP-VIII) RM

is the actual reach / nominal reach X

EXAMPLE:

$$I_0 = 3I_0$$

$$K_0 = 3$$

$$X = 0.95$$
; $(1-X) = 0.05$ {5% pull back}

$$\frac{2}{3} I_{\theta} Z_{R1} + I_{\theta} Z_{R1} = (18.1) (RM)$$

If
$$Z_{R1} = 3$$
 and $RM = 1$, then

$$\frac{5}{3}(I_{\theta})(3) = 18.1$$

$$I_{\theta} = 3.62 \text{ amps}$$

SPECIFICATIONS

DIMENSIONS

Height

14 inches (356 millimeters)

8 rack units

Width

19.1 inches (484 millimeters) Standard 19 inch rack

Depth

16 inches (406 millimeters)

WEIGHT

Standard rack-mounted unit weighs approximately 45 pounds (20 kilograms)